

Work Order No.: BCR/Pharm/104A/02/19-20

Date : 6th February, 2020

To,
Saroda Construction
Vidyasagar Pally
D-Block Exten.
Durgapur - 713213.

Sub. : Civil works for Rain Water Harvesting, beside college Building
inside Pharmacy campus.

Dear Sir,

This is to inform you that the above stated work had been awarded to you for a total amount of Rs. 1,09,649.00 (Rupees One lac Nine Thousand Six Hundred Forty Nine only) as per negotiation and agreed by you.


BOQ Schedule is attached herewith.


Terms & Contidions :


01. GST will be extra as applicable as per rules.
 02. The entire job has to be completed within 20th March, 2020.
 03. The payment will be certified after 100% satisfactory work done.
 04. The entire work will be looked by our Engineer-in-charge & before using the materials it must be approved by the Authority.
 05. The rates given in the schedule is final and no change is applicable in the future.
 06. All measurement shall be certified as per IS:1200.
 07. All item activity and work procedure & practice should be followed as per relevent codes and direction of Engineer-in-Charge (EIC).
Construction work of any item activity or all the construction activity may be interrupted during the
 08. construction period for any Technical scrutiny or for the decesion of Management / Technical team etc. Agency will have to co-operate in this situation without any commercial implication.
 09. Dispute settelement procedure (for incorporation): Normally through negotiations leading to amicable settlement. If dispute persists, settlement through arbitration under Arbitration and Conciliation Act, 1996 and any statutory modification, amendments or replacements thereof. Language of arbitration shall be English. This work order is governed by, takes effect and will be construed in accordance with the laws of India, and the parties irrevocably and unconditionally submit to jurisdiction of the appropriate courts at Durgapur.
 10. Agency is agreed, accepted and responsible to provide and arrange all necessary work safety PPE's, site safety supervisor. Daily safe work plan and action prior to start any construction works. However College authority will have the right to stop the entire work activity if any unsafe work execution is found during the schedule work.
- Please acknowledge receipt of this Work Order.

Thanking you.

Yours faithfully,


Treasurer


Prof. (Dr.) Samir Kumar Samanta
M. Pharm., Ph.D (J.U.)
Principal
Dr. B. C. Roy College of Pharmacy & AHS
Durgapur, West Bengal-713206



Name work: Civil works for Rain Water Harvesting, beside college Building inside Pharmacy campus.


Name of Agency: Saroda Construction


Date: 06-02-2020

Item no.	Item description	Unit	Qty	Rate	Amount in INR
1	Earth work in excavation for foundation and etc up to depth of 3.0 mtr. Asw per drawing and direction of Engineer in charge.	cum	48	120	5760
2	Back filling with excavated surplus soil in layers and compected by hand raming or mechanical means as per instructions.	cum	5	50	250
3	Providing sand filling in foundation & under floor etc complete with all labour & materials.	cum	0.5	805	402.5
4	Plain Cement concrete with graded stone chips 20mm & down to all levels in foundation, under floor etc complete with all labour & materials. a) PCC-1:2:4	cum	2.75	4690	12897.5
5	Reinforced Cement Concrete of Prop. 1:1.5:3 (1 cement, 1.5 coarse sand & 3 stone chips 20mm & down graded)	cum	0.5	6300	3150
6	Providing & fixing of shuttering works including provision of stout props in slab, beam, lintel, column, chajja etc striking out after completion.	sqm	3	300	900
7	250mm or more thick Brickwork in cement mortar 6:1 including scaffolding & other elementary works with all labour & materials complete. All joints should be filled with mortar on both side and having kyed or groove cutting for bonding of plaster finish.	cum	12	5300	63600
8	125mm thick Brickwork in cement mortar 4:1 with approved H.B.netting in every 3rd layer. All joints should be filled with mortar on both side and having key joint or groov cutting for bonding of plaster finish.	sqm	1	800	800
9	75mm thick Brickwork in cement mortar (3:1) with approved H.B. netting in alternate layer.	sqm	1	380	380
10	Plaster to all type of wall, concrete surface, floor etc with sand & cement mortar including rounding all corners, raking out joints, roughening of concrete surface and application of cement slurry etc complete with all labour & materials. With 6:1 Cement mortar a) 15mm thick.	sqm	50	151	7550
11	Neat cement punning in wall dado window Sills, floor, drain etc.	sqm	10	45	450
12	Supply, cutting, bending, placing at any level, binding in proper line and level of reinforcement steel work as per the approved drawing and direction of engineer (Recommended and approved make / brand of Reinforcement steel shall be used only).	Kg	50	59.5	2975
13	Charges for cutting and fixing of PVC pipe for weep holes.	Each	20	25	500
14	Transportation of debris, muck, bats, surplus soil etc by Tractor including loading, unloading spreading and levelling as per direction of EIC	Each Trip	24	350	8400
15	Supply and making of RCC precast slab with prop. of 1:1.5:3 as per direction	cum	0.2	8171	1634.2

Rupees One lac Nine Thousand Six Hundred Forty Nine only

Total 109649.20
Say 109649.00


Prof. (Dr.) Samir Kumar Samanta
M. Pharm., Ph.D (J.U.)
Principal
Dr. B. C. Roy College of Pharmacy & AHS
Durgapur, West Bengal-713206



Saroda Construction
Civil Contractor
Vidvasagar Pally
D-Block (Ext)
Durgapur-713213
Mobile : 9434534788/9733477755
GSTIN: 19AJKLP1470G1Z2

Original Buyer's Copy
Dr. B. C. Roy College of Pharmacy & AHS
Dr. Meghnad Saha Road,
Bidhannagar
Durgapur- 713206
West Bengal - 19

Invoice No

BCRP/RWH/2020-21/01- 1st & Final bill

Date: -11-07-2020

Work order Ref :

BCR/Pharm/104A/02/19-20,

Dt. 06-02-2020

Name of Work: **Civil works for Rain water Harvesting, beside college building inside Pharmacy College Campus.**

Item No.	Description	SAC	Unit	Qty.	Rate	Amount	CGST-9%		SGST-9%	
							Amount	Amount	Amount	Amount
1	Earth Work in excavation in foundation	995433	cu.m	70.76	120	8491.20	764.21	764.21	764.21	
2	Back filling the foundation trenches,	995433	cu.m	9.08	50	454.00	40.86	40.86	40.86	
4	a) PCC-1:2:4	995454	cu.m	2.45	4690	11490.50	1034.15	1034.15	1034.15	
6	Providing & fixing of shuttering in	995457	Sq.m	0.48	300	144.00	12.96	12.96	12.96	
7	Brick work 250mm thick or more.	995456	cu.m	10.33	5300	54749.00	4927.41	4927.41	4927.41	
10	15mm thick plaster 6:1	995454	Sq.m	59.79	151	9028.29	812.55	812.55	812.55	
11	Net cement punning...	995454	Sq.m	8.18	45	368.10	33.13	33.13	33.13	
12	Supply, cutting, bending, placing at	995478	Kg	30.38	59.5	1807.61	162.68	162.68	162.68	
13	Charges for cutting & fixing of PVC pipes..		Each	25	25	625.00	56.25	56.25	56.25	
14	Transportation of surplus soil...		Trip	24	350	8400.00	756.00	756.00	756.00	
15	Supply and making and fixing of RCC precast	995454	cu.m	0.24	8171	1961.04	176.49	176.49	176.49	
Extra	Supply & laying of Polythin sheet including cutting	995452	sq.m	21.19	11	233.09	20.98	20.98	20.98	
Total						97751.83	8797.66	8797.66	8797.66	

Payble amount including GST -97751.83+8797.66+8797.66=**Rs. 115347.16**

Total GST 18% =8797.66+8797.66= Rs. 17595.33

Rupees One Lakh Fifteen Thousand Three Hundred Forty Seven and paise sixteen Only

Bidyut Saha

Prof. (Dr.) Sanir Kumar Samanta

M. Pharm., Ph.D (U.U.)

Principal

Dr. B. C. Roy College of Pharmacy & AHS

Durgapur, West Bengal-713206



for, U. Khatun

P.O : BCR/Pharm/106/02/19-20

Date 25.02.2020



FROM:
DR. B. C. ROY COLLEGE OF PHARMACY AND AHS.
 Dr. Meghnad Saha Sarani, Bidhan Nagar,
 Durgapur-713206, Dist.- Paschim Bardhaman, W.B.
 Phone No. :0343-2532678/2532882, Fax No.0343-2532679
 E-mail :bcrcp_dgp@yahoo.co.in,Website:www.bccrcp.ac.in

TO:
M/S UDAIPUR MARBLES
 G.T.Road, Bhiringi, Durgapur-713203.
 Dist.: Paschim Burdwan. W.B. India
 Contact Person: Mr. Mukesh Agarwal.
 (M)9333744310,9434003695, Ph.No. 0343-2582622

GST NO.:19AABFU4321MIZZ

Sub: For Rain Water Harvesting (Wall Tiles Occasion Blue)

Quotation :

VERBAL

With reference to the above subject matter, we are pleased to place this order as per the terms & conditions stated and printed below.

Sl.No.	Particulars	Unit		Unit Price	Gross Amount (Rs)	Net Amount (Rs)
1	Wall Tiles Occasion Blue	110	box	254.24	27,966.40	27,966.40
2	Freight					600.00
Rupees Twenty eight thousand five hundred sixty six & Forty paise Only.						28,566.40

Terms and Conditions

1. Taxes and Duties
2. Delivery
3. Payment
4. Freight transport

GST as applicable at the time of delivery.
 Immediately from the date of receipt of firm order
 As per standard norms
 Will be extra as on actual basis.


M. Bhattacharya
 General Secretary

Dr. B. C. Roy COLLEGE PHARMACY AND AHS.

CC To

Manager (Finance), BCREC, Durgapur

[Signature]
 Prof. (Dr.) Samir Kumar Samanta
 M. Pharm., Ph.D (J.U.)
 Principal
 Dr. B. C. Roy College of Pharmacy & AHS
 Durgapur, West Bengal-713206



INVOICE CUM CHALLAN

ORIGINAL FOR BUYER

From : Phone : (0343) 2582622

UDAIPUR MARBLES

WHOLESALE & RETAILER

Pure Quality Makrana Marbles, Kota, Dholpur
Stones, Mosaic Materials, Glaze Tiles etc.

G. T. Road, Bhiringi (W), Durgapur - 713203, West Bengal

Consignee B. C. Roy Pharmacy College
Address Fulbari
Durgapur
Ship to _____
Address _____
Buyer's GSTIN _____ State Code 19
Invoice No. A 2782 Date 25.2.2020

Sl. No.	Qty.	PARTICULARS	HSN ACS	Rate		TOTAL	
						Rs. P.	
	110B	Wall tiles (Ocean Blue)	6907	254.24		27966.40	
		Delivery				600	
				Rate		28566.40	
			CGST	9%		2570.97	
			SGST	9%		2570.97	
			IGST				
			TOTAL			33708.34	
Transporter Name							
Vehicle No. <u>WB-39A/9869</u>							
Rupees : <u>Thirty three thousand seven</u>							

E-way bill no.
85109285 9829


[Handwritten signature]

hundred eight & thirty four paise only

GSTIN : 19AABFU4321MIZZ

E. & O. E.

For UDAIPUR MARBLES



Prof. (Dr.) Samir Kumar Samanta
M. Pharm., Ph.D (J.U.)
Principal
Dr. B. C. Roy College of Pharmacy & AHS
Durgapur, West Bengal-713206